

**BUILT-UP AIR HANDLING UNIT SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	SUPPLY AIR FAN *	CHILLED WATER COIL *	HEATING COIL *	HUMIDIFIER *	FILTER *	AIR FLOW		REMARKS
									SUPPLY AIR CFM	OUTSIDE AIR CFM	
L-CS-107-AH-01	LVEA BUILDING	LVEA	BUILT-UP	L-CS-107-SF-01 L-CS-107-SF-02	L-CS-107-CC-01 L-CS-107-CC-02	----	----	L-CS-107-AF-01	33,000	2,600	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-CS-107-AH-02	LVEA BUILDING	LVEA	BUILT-UP	L-CS-107-SF-03 L-CS-107-SF-04	L-CS-107-CC-03 L-CS-107-CC-04	----	----	L-CS-107-AF-02	33,000	2,600	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-CS-107-AH-03	LVEA BUILDING	OSB (LAB)	BUILT-UP	L-CS-107-SF-05 L-CS-107-SF-06	L-CS-107-CC-05 L-CS-107-CC-06	L-CS-107-HC-09 L-CS-107-HC-10	----	L-CS-107-AF-03	24,000	1,720	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-EA-203-AH-01	END STATION A	END STATION A	BUILT-UP	L-EA-203-SF-01 L-EA-203-SF-02	L-EA-203-CC-01 L-EA-203-CC-02	----	----	L-EA-203-AF-01 L-EA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-EB-203-AH-01	END STATION B	END STATION B	BUILT-UP	L-EB-203-SF-01 L-EB-203-SF-02	L-EB-203-CC-01 L-EB-203-CC-02	----	----	L-EB-203-AF-01 L-EB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL

NOTES:  
 1. FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES SEE SHEETS LA-H-001 AND LA-H-002.

\* SEE INDIVIDUAL EQUIPMENT SCHEDULES

**PACKAGED AIR-COOLED WATER CHILLER SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	CHILLED FLUID	DESIGN TEMP (*F DB)	AMBIENT ALTITUDE (FT)	MIN OPER TEMP (*F DB)	COMPRESSOR		MINIMUM CAPACITY (TONS)	MAX KW	REFRIGERANT	EVAPORATOR				CONDENSER		SINGLE POINT ELECT CONN		OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS	
								TYPE	DRIVER				ENT TEMP (*F)	LVG TEMP (*F)	GPM	MAX PD (FT)	NO. FANS EACH UNIT	HP EACH FAN	VOLTS/ PH/Hz	TOTAL RLA				TOTAL LRA
L-CS-190-CH-01	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-CS-190-CH-02	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-CS-190-CH-03	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY
L-EA-200-CH-01	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-EA-200-CH-02	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY
L-EB-200-CH-01	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-EB-200-CH-02	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY

**CHILLED WATER COOLING COIL SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	MAX FACE VEL (FPM)	ACFM	MAX AIR PD (IN. WG)	ROWS	MAX FPI	EAT				LAT				MAX WTR PD (FT)	MANUFACTURER/ MODEL NO.	OVERALL SIZE (IN. X IN.)	REMARKS
										*FDB	*FWB	*FDB	*FWB	*FDB	*FWB	*FDB	*FWB				
L-CS-107-CC-01	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	CARRIER BC	72 X 68	25% GLYCOL	
L-CS-107-CC-02	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	CARRIER BC	72 X 68	25% GLYCOL	
L-CS-107-CC-03	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	CARRIER BC	72 X 68	25% GLYCOL	
L-CS-107-CC-04	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	CARRIER BC	72 X 68	25% GLYCOL	
L-CS-107-CC-05	CORNER STATION	OSB	430	390	445	11,500	0.80	8	11	83.1	62.7	50.4	50.3	42	54.4	85	15	CARRIER BC	36 X 105	25% GLYCOL	
L-CS-107-CC-06	CORNER STATION	OSB	430	390	445	11,500	0.80	8	11	83.1	62.7	50.4	50.3	42	54.4	85	15	CARRIER BC	36 X 105	25% GLYCOL	
L-EA-203-CC-01	END STATION A	END STATION A	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	CARRIER BC	2(30 X 60)	25% GLYCOL	
L-EA-203-CC-02	END STATION A	END STATION A	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	CARRIER BC	2(30 X 60)	25% GLYCOL	
L-EB-203-CC-01	END STATION B	END STATION B	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	CARRIER BC	2(30 X 60)	25% GLYCOL	
L-EB-203-CC-02	END STATION B	END STATION B	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	CARRIER BC	2(30 X 60)	25% GLYCOL	

**EXPANSION TANK SCHEDULE**

UNIT NO.	LOCATION	SERVICE	TYPE	MIN CAP (GAL)	MAX WORKING PRESS (PSIG)	MAX OPER TEMP (*F)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
L-CS-107-TK-01	CORNER STATION	CHILLED WATER	DIAPHRAM	45	150	110	510	TACO CX170	CARBON STEEL CONSTRUCTION
L-EA-203-TK-01	END STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO CX84	CARBON STEEL CONSTRUCTION
L-EB-203-TK-01	END STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	TACO CX84	CARBON STEEL CONSTRUCTION

**AIR SEPARATOR SCHEDULE**

UNIT NO.	LOCATION	SERVICE	MIN CAP (GPM)	SIZE (IN.)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
L-CS-107-AS-01	CORNER STATION	CHILLED WATER	700	6"	750	BELL & GOSSETT R-6	
L-EA-203-AS-01	END STATION A	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	
L-EB-203-AS-01	END STATION B	CHILLED WATER	170	3"	200	BELL & GOSSETT R-3	

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.

NO.	DATE	BY	CHKD	ENGR	PROJ	DESCRIPTION
1	3-20-97	WJK	AA	AA	TDM	ISSUED FOR AS-BUILT
2	8-7-98	DJB				REVISED EXPANSION TANK SCHEDULE

ISSUED FOR CONSTRUCTION

DRAWN	CLP	11-15-96
CHECKED	MN	10-25-96
ENGINEER	AA	1-23-96
PROJ	TDM	11-15-96

**AS-BUILT DRAWINGS**

100 WEST WALNUT STREET  
PASADENA, CALIFORNIA

CALIFORNIA INSTITUTE OF TECHNOLOGY  
MASSACHUSETTS INSTITUTE OF TECHNOLOGY

LIGO-D960962-02-O

LASER INTERFEROMETER  
GRAVITATIONAL-WAVE OBSERVATORY  
SITE NO. 2 - LIVINGSTON, LOUISIANA

TITLE	HVAC EQUIPMENT SCHEDULES SHEET 1	SCALE	NONE	CONTRACT NUMBER	PP150969	PROJECT NUMBER	8094
SHEET NUMBER	LA-H-003	REVISIONS					

*Note 1, LIGO, 04/07/99 07:38:39 PM*  
LIGO-D960962-02-O