

BUILT-UP AIR HANDLING UNIT SCHEDULE

UNIT NO.	LOCATION	SERVICE	TYPE	SUPPLY AIR FAN *	CHILLED WATER COIL *	HEATING COIL *	HUMIDIFIER *	FILTER *	AIR FLOW		REMARKS
									SUPPLY AIR CFM	OUTSIDE AIR CFM	
L-CS-107-AH-01	LVEA BUILDING	LVEA	BUILT-UP	L-CS-107-SF-01 L-CS-107-SF-02	L-CS-107-CC-01 L-CS-107-CC-02	----- -----	----- -----	L-CS-107-AF-01	33,000	2,600	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-CS-107-AH-02	LVEA BUILDING	LVEA	BUILT-UP	L-CS-107-SF-03 L-CS-107-SF-04	L-CS-107-CC-03 L-CS-107-CC-04	----- -----	----- -----	L-CS-107-AF-02	33,000	2,600	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-CS-107-AH-03	LVEA BUILDING	OSB (LAB)	BUILT-UP	L-CS-107-SF-05 L-CS-107-SF-06	L-CS-107-CC-05 L-CS-107-CC-06	L-CS-107-HC-09 L-CS-107-HC-10	----- -----	L-CS-107-AF-03	24,000	1,720	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-EA-203-AH-01	END STATION A	END STATION A	BUILT-UP	L-EA-203-SF-01 L-EA-203-SF-02	L-EA-203-CC-01 L-EA-203-CC-02	----- -----	----- -----	L-EA-203-AF-01 L-EA-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL
L-EB-203-AH-01	END STATION B	END STATION B	BUILT-UP	L-EB-203-SF-01 L-EB-203-SF-02	L-EB-203-CC-01 L-EB-203-CC-02	----- -----	----- -----	L-EB-203-AF-01 L-EB-203-AF-02	13,200	840	CONTRACTOR WILL SUBMIT SHOP DRAWINGS SHOWING CONSTRUCTION DETAILS FOR APPROVAL

NOTES:
 1. FOR LEGEND, ABBREVIATIONS AND GENERAL NOTES SEE SHEETS LA-H-001 AND LA-H-002.

* SEE INDIVIDUAL EQUIPMENT SCHEDULES

PACKAGED AIR-COOLED WATER CHILLER SCHEDULE

UNIT NO.	LOCATION	SERVICE	TYPE	CHILLED FLUID	DESIGN TEMP (*F DB)	AMBIENT ALTITUDE (FT)	MIN OPER TEMP (*F DB)	COMPRESSOR		MINIMUM CAPACITY (TONS)	MAX KW	REFRIGERANT	EVAPORATOR			CONDENSER		SINGLE POINT ELECT CONN		OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS		
								TYPE	DRIVER				ENT TEMP (*F)	LVC TEMP (*F)	GPM	MAX PD (FT)	NO. FANS EACH UNIT	HP EACH FAN	VOLTS/ PH/Hz				TOTAL RLA	TOTAL LRA
L-CS-190-CH-01	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-CS-190-CH-02	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-CS-190-CH-03	CORNER STATION	CORNER STATION	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	190	296	R-22	53.3	42	367	15	17	1.5	460/3/60	163	896	16800	TRANE RTAA 240	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY
L-EA-200-CH-01	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-EA-200-CH-02	END STATION A	END STATION A	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY
L-EB-200-CH-01	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F)
L-EB-200-CH-02	END STATION B	END STATION B	AIR COOLED	WATER 40% GLYCOL	100	400	0°F	SCREW	ELECT MOTOR	59	77	R-22	54.8	42	105	15	8	1.1	460/3/60	112	229	4950	TRANE RTAA 70	ALL PERFORMANCE DATA ARE AT ACTUAL CONDITIONS, LOW AMBIENT (20°F), STANDBY

CHILLED WATER COOLING COIL SCHEDULE

UNIT NO.	LOCATION	SERVICE	TOTAL CAPACITY (MBH)	SENSIBLE CAPACITY (MBH)	MAX FACE VEL (FPM)	ACFM	MAX AIR PD (IN. WG)	ROWS	MAX FPI	EAT				LWT (*F)	LWT (*F)	GPM	MAX WTR PD (FT)	MANUFACTURER/ MODEL NO.	OVERALL SIZE (IN. X IN.)	REMARKS
										*FDB	*FDB	*FDB	*FDB							
L-CS-107-CC-01	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	TRANE	72 X 68	25% GLYCOL
L-CS-107-CC-02	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	TRANE	72 X 68	25% GLYCOL
L-CS-107-CC-03	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	TRANE	72 X 68	25% GLYCOL
L-CS-107-CC-04	CORNER STATION	LVEA	535	495	435	14,500	0.80	8	11	82.8	63.8	50.7	50.6	42	53.8	106	12	TRANE	72 X 68	25% GLYCOL
L-CS-107-CC-05	CORNER STATION	OSB	430	390	445	11,500	0.80	8	11	83.1	62.7	50.4	50.3	42	54.4	85	15	COLMAC	2(36 X 105)	25% GLYCOL
L-CS-107-CC-06	CORNER STATION	OSB	430	390	445	11,500	0.80	8	11	83.1	62.7	50.4	50.3	42	54.4	85	15	COLMAC	2(36 X 105)	25% GLYCOL
L-EA-203-CC-01	END STATION A	END STATION A	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	TRANE	2(30 X 60)	25% GLYCOL
L-EA-203-CC-02	END STATION A	END STATION A	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	TRANE	2(30 X 60)	25% GLYCOL
L-EB-203-CC-01	END STATION B	END STATION B	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	TRANE	2(30 X 60)	25% GLYCOL
L-EB-203-CC-02	END STATION B	END STATION B	460	420	460	11,400	0.85	8	11	85.7	64.6	50.5	50.4	42	53.5	95	10	TRANE	2(30 X 60)	25% GLYCOL

EXPANSION TANK SCHEDULE

UNIT NO.	LOCATION	SERVICE	TYPE	MIN CAP (GAL)	MAX WORKING PRESS (PSIG)	MAX OPER TEMP (*F)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
L-CS-107-TK-01	CORNER STATION	CHILLED WATER	DIAPHRAM	45	150	110	510	WHEATLEY WPA-170	
L-EA-203-TK-01	END STATION A	CHILLED WATER	DIAPHRAM	23	150	110	285	WHEATLEY WPA-084	
L-EB-203-TK-01	END STATION B	CHILLED WATER	DIAPHRAM	23	150	110	285	WHEATLEY WPA-084	

AIR SEPARATOR SCHEDULE

UNIT NO.	LOCATION	SERVICE	MIN CAP (GPM)	SIZE (IN.)	OPER WT (LB)	MANUFACTURER/ MODEL NO.	REMARKS
L-CS-107-AS-01	CORNER STATION	CHILLED WATER	700	6"	750	WHEATLEY TAS060	
L-EA-203-AS-01	END STATION A	CHILLED WATER	170	3"	200	WHEATLEY TAS030	
L-EB-203-AS-01	END STATION B	CHILLED WATER	170	3"	200	WHEATLEY TAS030	

This document and the design it covers are the property of PARSONS. They are loaned only with the borrower's expressed written agreement that they will not be reproduced, copied, loaned, exhibited, or used in any other way, except by written consent from PARSONS to the borrower.

LIGO-D960962-03-O

LASER INTERFEROMETER
 GRAVITATIONAL-WAVE OBSERVATORY
 SITE NO. 2 - LIVINGSTON, LOUISIANA

HVAC
 EQUIPMENT SCHEDULES
 SHEET 1

SCALE: NONE CONTRACT NUMBER: PP150969 PROJECT NUMBER: 8094

SHEET NUMBER: **LA-H-003**

PARSONS

100 WEST WALNUT STREET
 PASADENA, CALIFORNIA

LIGO

CALIFORNIA INSTITUTE OF TECHNOLOGY
 MASSACHUSETTS INSTITUTE OF TECHNOLOGY

ISSUED FOR CONSTRUCTION

DRAWN	CLP	11-15-96
CHECKED	MW	10-25-96
ENGINEER	AA	1-23-96
PROJ	TDM	11-15-96

AS-BUILT DRAWINGS

NO.	DATE	BY	CHKD	ENGR	PROJ	DESCRIPTION
3	5-21-99	AO	AA	AA	AA	ISSUED AS REVISED AS-BUILT
2	8-7-98	DJB	AA	AA	MDW	ISSUED FOR AS-BUILT
1	3-20-97	WJK	AA	AA	TDM	REVISED EXPANSION TANK SCHEDULE