

Laser Interferometer Gravitational - Wave Observatory
Ligo
Tube Bake Out
Bill of Materials - LIGO-D980061-C-W
Assembly "A3"
Portable 120/208 Volt, 3 Phase Service Assembly

Item Num.	Description	Manufacturer	Part No.	Req.	Unit	Material	Labor
A3-1	120/208V, 225A Panel 'A3'	See drawing D980062	Sub-Assembly 'A3-1'	1	lot	LIGO	Contractor
001	Unistrut frame	See drawing D980059	Assembly	1	lot	Contractor	Contractor
008	Amber Caution Light	Federal	Model 141ST	1	ea.	LIGO	Contractor
020	Seal Tight Flex for 15 KV Cable	See drawing D980060	3"	1	lot	Contractor	Contractor
021	Service Entrance Conduit	See drawing D980060	1 1/2" RGS	1	lot	Contractor	Contractor
022	Service Entrance Conductor	See drawing D980060	#1/0 CU Per NEC	1	lot	Contractor	Contractor
023	Grounding	As Required	Requirements	1	lot	Contractor	Contractor