




Plans for LIGO II

Gary Sanders
Caltech
LSC Meeting - LLO
March 2000



LIGO II Reach





LIGO II Reference Design Parameters / LIGO I Comparison

Subsystem and Parameters	LIGO II Reference Design	LIGO I Implementation
<i>Comparison With LIGO I Top Level Parameters</i>		
Strain Sensitivity [rms, 100 Hz band]	2×10^{-23}	10^{-21}
Displacement Sensitivity [rms, 100 Hz band]	$8 \times 10^{-20} \text{ m}$	$4 \times 10^{-18} \text{ m}$
Fabry-Perot Arm Length	4000 m	4000 m
Vacuum Level in Beam Tube, (Vacuum Chambers)	$< 10^{-6}$, ($< 10^{-7}$) torr	$< 10^{-6}$ torr
Laser Wavelength	1064 nm	1064 nm
Optical Power at Laser Output	180 W	10 W
Optical Power at Interferometer Input	125 W	5 W
Power Recycling Factor	80 x	30 x
Input Mirror Transmission	3%	3%
End Mirror Transmission	15 ppm	15 ppm
Arm Cavity Power Loss on Reflection	1%	3 %
Light Storage Time in Arms	0.84 ms	0.84 ms
Test Masses	Sapphire, 30 kg	Fused Silica, 11 kg
Mirror Diameter	28 cm	25 cm
Test Mass Pendulum Period	1 sec	1 sec
Seismic Isolation System	Active/Passive, 6 stage	Passive, 4 stage
Seismic Isolation System Horizontal Attenuation	10^{-8} (10 Hz)	$\approx 10^{-5}$ (100 Hz)
Maximum Background Pulse Rate	1 per 10 years, triple interferometer coincidence	1 per 10 years, triple interferometer coincidence




The Real Goals

- Physics - “would be surprising if don’t see many sources” - Thorne yesterday
- Instrumental - quantum limited interferometer across entire sensitive band




LIGO II and LIGO I Sensitivity





Noise Anatomy of LIGO II



- 1 LIGO I total
- 2 Filtered seismic noise
- 3 Suspension thermal noise
- 4 Internal thermal noise - sapphire
- 5 Internal thermal noise - fused silica (fallback)
- 6 Shot noise
- 7 Radiation pressure noise
- 8 LIGO II total



The Scenario

YEAR	LIGO I	LIGO II
2000	Installation and commissioning	R&D
2001	Installation and commissioning	R&D
2002	Science run starts	MRE/R&D funds start, R&D, design, long lead items
2003	Science run	R&D, design, fabrication
2004	Science run	Fabrication, on-site assembly
2005	LIGO I interferometers removed	Fabrication, on-site assembly, installation into vacuum system
2006		Installation and commissioning



LIGO Laboratory and LSC Role

- LIGO Laboratory will organize and manage the LIGO II project
- LSC participation in the construction of LIGO II will be governed by Memoranda of Understanding (MOU) and specific, periodic Attachments describing tasks, funding, milestones and personnel, with subcontracts
 - » this model used successfully with Univ. of Florida during LIGO I
 - » this model used with LSC for R&D activities, without subcontracts

LSC is driving the LIGO II scientific goal and concept

- GEO is proposing a collaborating role and a capital contribution role
- ACIGA role developing (recent)



LSC and Lab Submitted Conceptual Documents

- September White Paper on Advanced Detector R&D
 - » Working Group chairs and spokesperson represented you well
 - this exercise is a success of the LSC structure and governance
- Conceptual Project Book prepared by Lab staff working with the LSC leadership
 - » Assumed all 3 interferometers replaced in 2005-2006 !
 - » Therefore all of LIGO I is turned off
 - » Assumed maximum possible choices of all options
 - intended to get cost envelope **bracketed**
 - » Cost estimate is MRE request \$94 million + GEO proposed contribution + contribution from LIGO Lab Operations budget!
 - Larger cost than expected due to active isolation, number of control loops and data acquisition/analysis complexity



Major Project Options

- How many interferometers to upgrade?
 - » Assume all 3 interferometers upgraded
- Convert the Hanford 2 kilometer to a 4 kilometer?
 - » Assume length is increased
- Upgrade done in one phase?
 - » Assume all 3 interferometers upgraded in one parallel installation
 - » **Decision on this may interact with other gravitational wave detectors to insure that observational coverage is considered**
 - » **Phasing of upgrade is a major scientific decision**



My Summary of NSF Review Recommendations

- LIGO Lab should proceed with full construction proposal for LIGO II to be submitted late in 2000
- NSF should establish a framework for evaluating R&D proposals related to LIGO II in order to assure coordination and monitoring
- LIGO Lab should submit an integrated R&D plan for Lab and LSC research in 2000 and 2001
- Construction proposal should identify Preconstruction R&D to begin in 2002
- Meaningful LIGO I data analysis results should be in hand prior to turning LIGO I off



LIGO Lab's Plan

- Integrated R&D Plan for 2000 and 2001 submitted this week
- Full LIGO II Proposal to be submitted near end of 2000, with LSC and GEO participating
- Request R&D \$ increment for 2002
- Request construction \$ for 2003
- Plan first installation in vacuum system in 2005




Activities

Navigation icons: Back, Next, Home, Dir., Hint, Help

Activity icons: Gantt, PERT, WBS, etc.

Layout - Classic WBS Layout_LIGO



General Status Resources Predecessors Successors Actv Codes/Roles Notebooks Steps Feedback Ref Docs Expenses Summary

Activity: A2120 Laser development industrial partners selected Project: LIGO_Lab

Duration	Planned: 0.0d	Actual: 0.0d	Remaining: 0.0d	At Cmplt: 0.0d	Status	<input type="checkbox"/> Started: 15-May-00 Physical %: 0% <input type="checkbox"/> Finished: 15-May-00 Exp Finish:	<input type="checkbox"/> Labor Units Budgeted: 0h Actual: 0h Remaining: 0h At Cmplt: 0h
Free Float		Constraint	Start On or After		Total Float	Constr Date	15-May-00



Management of the R&D

- LIGO Lab is working with LSC Working Group Chairs to define and monitor R&D program
- Fully integrated schedule of Lab and LSC activities is in preparation
- MOU's/Attachments B, C, D updated to agree with this plan
- LSC will host monthly progress telecons with LIGO Lab participating to assess progress and to identify issues



Since September, 1999 White Paper

- R&D White Paper failed to fully consider thermal noise sources
- Braginsky et al and Thorne et al papers on thermoelastic damping change sapphire perspective
 - » goal is to work this result into R&D and into LIGO II design choices
 - » increased emphasis on measuring thermal noise limits with suspended sapphire optics
- Some R&D is being curtailed or accelerated to focus on the LIGO II goals
- R&D program is undergoing greater discussion and coordination
 - » Aspen workshop was intense.....!



R&D Questions for This Meeting

- How much risk can we tolerate from limits of our knowledge of the LIGO II thermal noise floor?
 - » How well can we measure thermoelastic noise?
 - Direct measurement in suspended mass interferometers with fine displacement sensitivity (TNI,...)
 - Tabletop measures of damping (anelastic tests,...)
 - » Other contributions to thermal noise
 - Brownian motion noise
 - Young's modulus response to thermal fluctuations (G. Cagnoli)
 - Index of refraction response to thermal fluctuations (B. Kells)
 - others...
- We need the best plan we can define
- This is not a zero risk endeavor



R&D Questions for This Meeting

- Signal tuned configuration research
 - » 10 m Glasgow system
 - to prove the principle
 - » 40 Meter system
 - to shakeout an engineering implementation
- How come we measured phase sensitivity for LIGO I and no plan to do this for LIGO II is in our White Paper?
 - » Did not consider path length fluctuations induced by thermal fluctuations driving refractive index
 - » ACIGA role?
- How to integrate opportunities from all the test interferometers in the community?



This Year: Towards Full LIGO II Proposal

- Team forming in LIGO Lab
- Integrated plan being assembled
- Schedule for proposal preparation forming
- Seismic isolation decision **MUST** be made in April!
- Monthly R&D telecons to start for 3 working groups
- Schedule/cost estimating this summer
- Document complete in October
- LSC full participation is crucial as this is your detector vision
- Lot's of competition pounding the NSF door !
 - » Our field will be held to its own high standards