



---

# Staged approach to Advanced LIGO implementation

P Fritschel, D Coyne

3 May 2002



# Staged vs full upgrade

---

- Advanced LIGO interferometers were originally thought of as a series of upgrade steps
- This concept overtaken by the ‘full-upgrade’ approach, mostly to limit excursions into the vacuum
- Given the long time frame of the scenarios presented at the LSC meeting, we should revisit our strategy for implementing the full upgrade
- Is there a subset of the full upgrade that could be installed, giving an interesting sensitivity increase, without moving too far from the full path ?



# Target low frequency noise


---

- Initial LIGO limited by suspension thermal noise + seismic noise
- What if we installed only active seismic isolation + quad/triple suspensions ?
  - » Use initial LIGO core optics (spares)
    - Must interface to quad suspension design
  - » Use initial LIGO pre-stabilized laser
  - » Initial LIGO sensing/controls system
    - With modifications to actuation interfaces
  - » Mode cleaner? Probably upgrade as well



# Sensitivity: 100x in $R^3$

Inspiral Range: *initial* 13 Mpc  $\Rightarrow$  *intermediate* 60 Mpc  $\Rightarrow$  *advanced* 210 Mpc




LIGO-G020230-00-M

- Internal thermal:
  - $\phi = 10^{-7}$
- 6 W input power
  - shot noise doesn't include any detection inefficiency
- Suspension thermal noise as in AdLIGO
- Radiation pressure overestimated
  - 10 kg instead of 40 kg

# Use of initial LIGO core optics

- Avoids long lead time of sapphire optic fabrication
- Interface to quad suspension:
  - » Still want a 40 kg final mass
  - » Need a way to attach fused silica fibers
  - » Some sort of cradle for the 10 kg mirror:
- Cradle-to-mirror interface
  - » Don't know best design
  - » Clearly carries some risk of noise generation
  - » Can be tested in LASTI





# Detection Rate Impact

- Interpolating from K Thorne's Feb 2001 NSF presentation:

Source	Initial LIGO	Intermediate	Advanced
NS-NS	1 / 3000 yrs to <b>1 / 3yrs</b>	1 / 30 yrs to <b>1 / 10 days</b>	<b>1 / yr to 2 / day</b>
NS-BH	< 1 / 2500 yrs to <b>1 / 2yrs</b>	< 1 / 25 yrs to <b>1 / wk</b>	<b>&lt; 1 / yr to 4 / day</b>
BH-BH	< 1 / 300 yrs to <b>~1 / yr</b>	< 1 / 3 yrs to <b>~2 / wk</b>	<b>&lt; 2 / month to ~10 / day</b>
Stochastic BG	$\Omega > 10^{-5}$	$\Omega > 5 \times 10^{-9}$	$\Omega > 5 \times 10^{-9}$




# Schedule implications

- Schedule options discussed on the last day of the last LSC meeting are not driven by advanced LIGO COC schedule
  - » Proposed use of LIGO-1 COC does not enable an earlier start compared to these options – it is an alternative
- If we take more risk, we can bring the installation start back to Nov05
- Reduction in the initial commissioning length has not been estimated as yet
  - » Might expect 18 months to reduce to 12 months (in a paper exercise at least)

	Options	proposal submission	MRE \$ available	start install	1st Obs on-line	2nd Obs on-line
-1	Aug/2001 LSC	4Q2001	4Q2003	Jan-06	Dec-08	Dec-08 (Jun-10)
0	Mar/2002 LSC	4Q2002	1Q2005	Jun-07	Apr-09	Feb-11
1	both observatories in parallel			Jun-07	Apr-09	Apr-09
2	+ purchase core optics early			Mar-07	Jan-09	Jan-09
3	+ parallel (or no) first article test at LASTI			Nov-06	Sep-08	Sep-08
4a	+ production SEI < (MRE, LASTI cavity test)			Sep-06	Jul-08	Jul-08
4b	+ production SUS < (LASTI cavity test)			Jan-06	Nov-07	Nov-07
5	{1,3,4a} + Upgrade SEI & SUS only; Plan to use LIGO-1 COC			Sep-06	?	?
6	{5} + SUS production start < LASTI cavity test			Jan-06	?	?
7	{6} + no delay between stand-alone noise SUS test & production (was 3 mo) + 1st IFO SEI set ready in 16 mo (not 17)			Nov-05	?	?

ID	Task Name	Duration	Start	Finish	2003			2004				2005				2006		
					Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1	Q2	Q3	Q4	Q1		
1	MRE Proposal submitted	0 d	10/1/2002	10/1/2002			◆ 10/1											
2	MRE funding available	0 d	4/1/2005	4/1/2005														◆ 4/1
3	<b>Seismic Isolation (SEI)</b>	<b>1640 d</b>	<b>5/29/2000</b>	<b>9/8/2006</b>														
4	prototype	24 mons	5/29/2000	3/29/2002	3/29													
5	DRR	0 d	1/16/2001	1/16/2001														
6	Prelim Design	36 mons	1/16/2001	10/20/2003														
7	pathfinder fab (HAM)	10 mons	9/2/2002	6/6/2003		9/2												
8	PDR (HAM)	0 d	10/10/2003	10/10/2003														◆ 10/10
9	pathfinder fab (BSC)	10 mons	11/25/2002	8/29/2003		11/25												
10	PDR (BSC)	0 d	1/23/2004	1/23/2004														◆ 1/23
11	Final Design	10 mons	10/13/2003	7/16/2004														
12	FDR	0 d	7/16/2004	7/16/2004														◆ 7/16
13	Fab Readiness Rev	0 d	7/16/2004	7/16/2004														◆ 7/16
14	production	28 mons	7/19/2004	9/8/2006														
15	first article avail	0 d	2/25/2005	2/25/2005														◆ 2/25
16	sufficient qty to start install	0 d	11/4/2005	11/4/2005														◆ 11/4
17	<b>Core Optics Components (COC)</b>	<b>1382 d</b>	<b>12/4/2000</b>	<b>3/21/2006</b>														
31	<b>Suspension (SUS)</b>	<b>1377 d</b>	<b>9/20/2001</b>	<b>12/29/2006</b>														
32	DRR	0 d	9/20/2001	9/20/2001														
33	Preliminary Design	30 mons	9/20/2001	1/7/2004														1/7
34	non-TM Controls Prototypes Fab	6 mons	3/7/2002	8/21/2002														8/21
35	TM Controls Prototypes Fab	9 mons	5/30/2002	2/5/2003														2/5
36	non-TM PDR	0 d	2/5/2003	2/5/2003														◆ 2/5
37	non-TM Final Design	6 mons	2/6/2003	7/23/2003														2/6
38	TM PDR	0 d	5/14/2004	5/14/2004														◆ 5/14
39	TM Final Design	26 mons	5/17/2004	5/12/2006														5/17
40	TM 'noise' prototype fab	6 mons	5/17/2004	10/29/2004														5/17
41	non-TM 'noise' prototype fab	6 mons	9/18/2003	3/3/2004														9/18
42	FDR	0 d	4/22/2005	4/22/2005														◆ 4/22
43	production	22 mons	4/25/2005	12/29/2006														4/25
44	Assembly	10 mons	8/15/2005	5/19/2006														8/15
45	first article completed	0 d	11/4/2005	11/4/2005														◆ 11/4







# Summary of pros & cons

---

- Pros

- » Earlier installation of an upgrade with a significant performance improvement
- » Shorter commissioning time
- » Experience with the *'intermediate interferometer'* could make a valuable impact on the remaining *'advanced interferometer'* design

- Cons

- » Requires a second excursion into the vacuum system to get to the full upgrade
- » All (or most) suspended optics would need to be replaced for the full upgrade