Hydraulic External Pre-Isolation Progress on the Seismic Retrofit

Rich Abbott, Graham Allen, Drew Baglino, Colin Campbell, Daniel DeBra, Dennis Coyne, Jeremy Faludi, Peter Fritschel, Amit Ganguli, Joe Giaime, Marcel Hammond, Corwin Hardham, Gregg Harry, Wensheng Hua, Jonathan Kern, Brian Lantz, Ken Mailand, Ken Mason, Rich Mittleman, Jamie Nichol, David Ottaway, Joshua Phinney, Bill Rankin, Norna Robertson, Ray Scheffler, David Shoemaker, Oddvar Spjeld, and the Livingston Staff, LIGO CDS









News Headlines

Two similar systems with different actuator types tested at LASTI, both work!

Actuators for LLO will be Hydraulic (announced June '03)

Installation to begin after S3

Key ideas of the External Pre-Isolators (EPI)

- •Anthropogenic ground motion at LLO problematic, requires a fix.
- •Control the support table (base of the passive stack) in all 6 DOF.
- •Use active feedback to control the support table
 - •Displacement sensors at low frequencies
 - •Inertial sensors at high frequencies (sometimes)
 - •Blend between high and low is ~0.5 Hz to 1.0 Hz
- •Correct the displacement sensors with ground motion sensors
- •Isolate all three translational DOFs from microseism to $\sim 10 \text{ Hz}$
- •Cause minimal disruption to the interferometer
- •Achieve necessary performance from .15 Hz to 3 Hz

Placement of an External **Isolation System**

- Replace the coarse and fine actuators.
- Isolate the stack input in all 6 DOF.





Placement of the Actuators and Offload Springs



All the pier-top components are mounted into a frame

Frame holds:

1 vertical and 1 tangential actuator, (isolation and alignment in 6 DOF)
Pair of offload springs and initial alignment fixtures
Sensors which are not included in the actuators

5

Implementation in 6 DOF

Piers support the payload (blue)EPI system frame (purple) atop the pierEPI controls the support table (green)Stack (not shown) sits on the support table



Implementation in 6 DOF

Piers support the payload (blue) EPI system frame (purple) atop the pier EPI controls the support table (green) Stack (not shown) sits on the support table



Two types of actuators under test at LASTI



Installation

Do not open the vacuum chambers. Do not disturb the alignment of the installed optics. Do not drop the baby.

- 1. Instrument the position of the support table
- 2. For each corner, lift the crossbeam weldment (.010") with the crane and manual screwjack
 - a) Lower the scissor jack
 - b) Remove the old coarse and fine actuators
 - c) Install the new frame and actuators
 - d) Align the frame, align the payload, align the sensors & actuators
- 3. With all 4 new corners installed, iterate the alignment with the offload springs and coarse actuation system. (.001")





HAM Installation



LIGO-G030414-00-R

CAD rendering by Hytec, photographs courtesy of Ken Mason

10

Adding External Crossbeams to HAM Chamber



BTL August '03 LSC photo: Den



Hydraulic Installation









Commissioning of the Hydraulic system

Preliminary results

Bandwidth of 10 Hz

Blended sensors in the vertical direction, using – corrected displacement sensors, and inertial feedback geophones, blended at 0.8 Hz

Loops in the coordinate basis (x, y, z, pitch, roll, yaw, O.C.)

Close all 6 DOF

Reasonable isolation at target frequency

Performance in X



Match of trans&ratio indicates limits are loop gain and correction match.

Performance in Y



Performance in Z



January data for z direction, a good set of data. Top plot shows ASDs of motion: Ground (blue) Support table with control on (green)

Lower plot shows ratios: Transmission with control off (blue) Transmission with control on (green)

Peak above 1 Hz is ADC noise Performance not always this good – Coupling between payload motion and the ground motion STS-2?

Status of Tasks

Ground motion sensors – in place geophones & displacement sensors – ordered values - in production (last one arrives 12/03) calibration ready Sept., finished by March springs – production began yesterday actuator machining – internal reviews done, ready to make actuator delivery – Dec 9 – Feb 9 housings – submitted to NSF, delivery end of Nov. pump station – updating design, review ~Sept 8 plumbing – being laid out, review ~Oct 1 control electronics – LASTI system installed, in testing Installation (slip free) – Jan – April 03

ID 1	Task Name HEPI	Duration	Start Mon 10/7/02	Finish Predecessors Half 2, 2003 Half 1, 2004 Thu 4/3/03 M J J A S O N D J F M A M	
67	PDR	96 days	Thu 1/2/03	Fri 5/16/03 100%	
68 69	release documents	0 days 1 day	Thu 1/2/03 Fri 4/18/03	Thu 1/2/03 58 Fri 4/18/03 68FS+2 wks	
70	final decision	0 days	Fri 5/16/03	Fri 5/16/03 69FS+4 wks Mon 10/20/03 00/	
72	Pump Station FDR	28 days	Mon 8/11/03	Wed 9/17/03	
73 74	release documents	14 days 7 days	Mon 8/11/03 Fri 8/29/03	I nu 8/28/03 0% Mon 9/8/03 73	
75 76	final decision Distribution System FDR	7 days	Tue 9/9/03	Wed 9/17/03 74 Mon 10/20/03 75	
70	finalize design pkg/dws	23 days 2 wks	Thu 9/18/03	Wed 10/1/03 75	
78 79	docs released review	0 days 1 day	Wed 10/1/03 Thu 10/9/03	Wed 10/1/03 77 10/1 Thu 10/9/03 78FS+1 wk 10/1 10/0	
80 81	incorporate recommendations of review	7 days	Fri 10/10/03	Mon 10/20/03 79 0%	
82	finalize design pkg/dws	15.4 wks	Thu 5/1/03	Fri 8/15/03	
83 84	docs released Production	0 days 259 days?	Fri 8/15/03 Wed 5/7/03	Fri 8/15/03 82 Mon 5/3/04 2%	
85 86	CCB decision on production	1 day	Mon 5/19/03	Mon 5/19/03 70	
80	EPI: order long lead items	141 days?	Wed 5/7/03	Wed 11/19/03 58 Wed 11/19/03 58 Wed 11/19/03 88%	
88 89	L4C geophones receive L4C	1 day 0 days	Wed 8/6/03 Wed 11/19/03	Wed 8/6/03 85 Wed 11/19/03 88FS+15 wks	
90 91	displacement sensors	1 day	Mon 7/21/03 Mon 11/3/03	Mon 7/21/03 85	
92	Maraging Steel order	1 day?	Wed 5/7/03	Wed 5/7/03 I 100%	
93 94	receive maraging steel HEPI: Pump Station production	1 day? 81 days	Thu 7/31/03 Thu 9/18/03	Thu 7/31/03 92FS+12 wks Thu 1/8/04 85	
95 96	order pumps (7)	1 day 0 days	Thu 9/18/03 Thu 12/11/03	Thu 9/18/03 75	
97	order reservoirs (7)	2 days	Fri 9/19/03	Mon 9/22/03 9575	
98	order machined parts	2 days	Mon 11/17/03 Thu 9/18/03	Mon 11/1 //03 9/FS+8 wks Fri 9/19/03 75	
100 101	receive machined parts order misc COTS parts	0 days	Fri 11/14/03 Thu 9/18/03	Fri 11/14/03 99FS+8 wks Wed 9/24/03 75	
102	receive COTS parts	0 days	Wed 11/5/03	Wed 11/5/03 101FS+6 wks	
103	obtain assembly quotes assembly & air leak testing	2 wks 3 wks	Fri 12/12/03	Wed 10/1/03 75 Thu 1/1/04 103,96,98,100,102	
105 106	ship to LLO HEPI: Actuator Isolation Valve Tree	1 wk	Fri 1/2/04 Thu 9/18/03	Thu 1/8/04 104	
107	finalize design pkg/dws	2 wks	Thu 9/18/03	Wed 10/1/03 75	
108 109	order valves and fittings (48)	1 wk 1 day	1 nu 10/2/03 Thu 10/9/03	West 10/00/03 IO/00/04 Thu 10/9/03 108	
110 111	receive valves and fittings assembly & He leak testing	6 wks 4 wks	Fri 10/10/03 Fri 11/21/03	Thu 11/20/03 109 Thu 12/18/03 110	
112	HEPI: Fluid distribution system production	78 days	Tue 10/21/03	Thu 2/5/04 85	
113 114	receive distribution manifolds	3 days 0 days	Thu 12/4/03	Thu 12/4/03 113FS+6 wks	
115 116	leak test manifolds obtain plumbing quotes	1 wk 3 wks	Fri 12/5/03 Tue 10/21/03	Thu 12/11/03 114	
117	award plumbing contract	0 days	Mon 11/10/03	Mon 11/10/03 116	
118 119	install Y end station	2 wks	Fri 12/19/03 Fri 1/2/04	Thu 1/15/04 118,111,115	
120 121	install corner station HEPI: hydraulic actuator production	3 wks 250 days	Fri 1/16/04 Tue 5/20/03	Thu 2/5/04 119,111,115 Mon 5/3/04 85	
122	finalize dwg pkg	8 wks	Tue 5/20/03	Mon 7/14/03 85	
123	get quotes	24 days 2.5 wks	Tue 5/20/03	Thu 6/5/03 70 0%	
125 126	order ~100 servo-valves order ~500 nozzles	1 day 8 wks	Mon 7/14/03 Fri 7/11/03	Mon 7/14/03 70 Thu 9/4/03 70	
127	insert nozzles & test (Parker)	8 wks	Tue 12/16/03	Mon 2/9/04 126,128	
128	Calibrate servo valves	50 days	Tue 1/6/04	Mon 3/15/04 128FS+15 days 0%	
130 131	order bellows receive bellows	1 day 10 wks	Wed 8/20/03 Thu 8/21/03	Wed 8/20/03 70,123 Wed 10/29/03 130	
132	Contract let by Caltech	5 days	Mon 8/11/03	Fri 8/15/03 86	
133	receive machined parts	16 wks	Tue 8/19/03	Mon 0/10/00 DS Mon 12/8/03 133	
135 136	get quotes for welded assy award assy contract	2.5 wks 0 days	Mon 8/18/03 Wed 9/3/03	Wed 9/3/03 123 Wed 9/3/03 135,86FS+10 days	
137	welded assembly	21 wks	Tue 12/9/03	Mon 5/3/04 136,1285S+2 wks,131,134,127SS-6 wks	
139	units become available	17 wks	Tue 1/6/04	Mon 5/3/04 138SS+3 wks 0%	
140 141	EPI Spring Production finalize dwg pkg	102 days 2 wks	Thu 7/10/03 Thu 7/17/03	Fri 11/28/03 70 12% Wed 7/30/03	
142	DCN act subtos	12 days	Thu 7/31/03	Fri 8/15/03 141	
143	Order production	0 wks	Fri 8/15/03	Fri 8/15/03 142,83	
145 146	machine parts EPI Actuator,Sensor & Spring bracket production	15 wks 79 days	Mon 8/18/03 Thu 7/10/03	Fri 11/28/03 0% Tue 10/28/03 0%	
147 148	finalize dwg pkg DCN	0.8 wks	Fri 7/25/03	Wed 7/30/03 Imm 70% Tue 8/19/03 147	
149	get quotes	0 wks	Thu 7/10/03	Thu 7/10/03 ← 7/10	
150 151	Order Production machine parts	0 wks 10 wks	Tue 8/19/03 Wed 8/20/03	Tue 8/19/03 148 Tue 10/28/03 83,150	
152 153	EPI Boot (machined Foot) Production	95 days	Mon 6/23/03	Fri 10/31/03 0%	
154	review & DCN	1 wk	Mon 8/18/03	Fri 8/22/03 153	
155 156	yet quotes for machining order boot	1 wk	Mon 7/7/03 Mon 8/25/03	Mon 8/25/03 154,83	
157 158	receive machined parts HEPI: Flow bench for calibrating Parket valves	10 wks 107 days?	Mon 8/25/03 Fri 8/29/03	Fri 10/31/03 156SS Mon 1/26/04 0%	
159	finalize design of complete test fixture	3 wks	Fri 8/29/03	Thu 9/18/03	
161	Assemble	3 wks	Tue 9/30/03	Mon 10/20/03 160	
162 163	ship to LLO Assemble sensors, pump and test fixture	1 wk 15 days	Tue 10/21/03 Tue 10/28/03	Mon 10/27/03 161 Mon 11/17/03 162	
164 165	Calibrate ~100 valves	50 days?	Tue 11/18/03	Mon 1/26/04 163 0%	
166	finalize dwg pkg	8 wks	Tue 7/1/03	Mon 8/25/03	
167 168	DCN get quotes	14 days 0 wks	Tue 8/26/03 Thu 7/10/03	Fri 9/12/03 166 Thu 7/10/03 ↓ 7/10	
169 170	Release drawing for production machine parts	1 day?	Mon 9/15/03 Tue 9/16/03	Mon 9/15/03 167 Mon 11/24/03 83,169	
171	EPI Actuator Housing Production	111 days	Mon 6/23/03	Mon 11/24/03	
172 173	inalize awg pkg review & DCN	8 wks	Mon 6/23/03 Mon 8/18/03	Fri 8/22/03 172 0%	
174 175	get quotes for welded assy award assy contract	2 wks 5 davs	Mon 8/4/03 Wed 8/20/03	Fri 8/15/03 100% Tue 8/26/03 174,86FS+10 days	
176	Release drawing for production	1 day	Wed 8/27/03	Wed 8/27/03 83,173,175	
177 178	veceive machined parts	10 wks 2 wks	vved 8/27/03 Wed 11/5/03	Tue 11/18/03 177	
179 180	1st set available VME System	14 days 140 days	Wed 11/5/03 Mon 5/19/03	Mon 11/24/03 178SS,151,157,142	
181	to be detailed	7 mons	Mon 5/19/03	Fri 11/28/03 0% 0% 0%	
182 183	ready to start	80 days	Thu 1/8/04 Thu 1/8/04	Ind 4/23/04 0% Thu 1/8/04 118,105,89,91,140,93,179,139SS,164SS+2 wks,181 0%	
184 185	install X-end mechanicals Install Y-end mechanicals	2 wks 3 wks	Fri 1/9/04 Fri 1/23/04	Thu 1/22/04 183 Thu 2/12/04 184	
186	Install BSC	2 wks	Fri 2/13/04	Thu 2/26/04 185	
187 188	Install H2	3 wks 2 wks	⊢ri 2/27/04 Fri 3/19/04	100 37 10704 100 Thu 4/1/04 187	
189 190	Install H3 Install H4	2 wks 2 wks	Fri 4/2/04 Fri 4/16/04	Thu 4/15/04 188 Thu 4/29/04 189	
191	Commissioning	83.25 days?	Thu 1/8/04	Wed 5/5/04	
192 193	X-end	0 days 1.5 wks	Fri 1/23/04	Tue 2/3/04 1/8 Tue 2/3/04 184,181,118	
194 195	Y-end ITMx	1.5 wks 1.5 wks	Fri 2/13/04 Fri 2/6/04	Tue 2/24/04 185,181,119 Tue 2/17/04 181,120	
196	ITMy	1.5 wks	Fri 2/6/04	Tue 2/17/04 181,120	
197 198	вос H1	1.5 wks 1.5 wks	⊢ri 2/27/04 Fri 3/19/04	Tue 3/30/04 187,181,120	
199 200	H2 H3	1.5 wks 1.5 wks	Fri 4/2/04 Fri 4/16/04	Tue 4/13/04 181,188,120 Tue 4/27/04 181,189,120 0% 0%	
201	H4	1 day?	Fri 4/30/04	Fri 4/30/04 181,190,120	
202		Z.20 UZYS	101011 5/3/04		
Project: Date: Sa	M020142-06_snipit t 8/16/03 Critical Solit	Critical Progress		Split • • • • • • • • • • • • • Baseline Baseline Milestone Summary Progress Project Summary External Milestone Task Progress Baseline Split Milestone Summary External Taske Deadline	
		1 034			

To Conclude

We can install an external isolation system with minimal disruption to the LIGO optics.

We have achieved $\sim 10x$ isolation performance from the microseism to ~ 2 Hz, partly covering the problematic frequency band.

We can easily track the tidal motion.

Modifications the HAM simplify the installation and control.

LIGO engineers have been cranking out designs and drawings.

We are eager to begin installation after S3.

How to maintain Alignment, and have Isolation from the Ground



How to maintain Alignment, and have Isolation from the Ground



How to maintain Alignment, and have Isolation from the Ground



Commissioning of the Electromagnetic System

Preliminary results

Bandwidth of 10 Hz

Blended sensors, using – corrected displacement sensors, and inertial feedback geophones, blended at 0.5 – 0.7 Hz

Loops in the coordinate basis (x, y, z, pitch, roll, yaw, O.C.)

Close all 6 DOF

Reasonable isolation at target frequency

Preliminary Performance in X Electromagnetic system on HAM



23

LIGO-G030414

Preliminary Performance in Z Electromagnetic system on HAM



Ottoway 24

Improvement in the bending mode

Colocated Horizontal Geophone Transfer Function



Comparison of the sites

red=livingston, green=hanford



LIGO-G030414-00-R

BTL August '03 LSC

Design Trades



Hydraulic Valve forms the bridge

- Differential bridge in a single valve body
- 4 nozzles one for each resistor in the bridge
- Original nozzles replaced with custom units shown below right.



Parker DYP-2S valve



The new nozzle



LIGO-G030414-00-R

BTL August '(

Quiet Hydraulic Actuator 00 00 munical \mathcal{O} 0

Controller



Histograms of the ground motion

2 years of data compiled by Ed Daw 1-3 Hz BLrms monitor

We appear to need a factor of 10 isolation in the 1-3 Hz band.

Many caveats to this, please see Ed's talk tomorrow at 10 in D.C.



Program Overview

- Ground motion issues:
 - @ LLO
 - Steady-state ambient noise is higher due to anthropogenic sources; Transients, particularly from logging.
 - Impossible to hold the interferometers locked reliably during the day.
 - @ LHO
 - Wind induced seismic noise at LHO exceeds locking threshold at ~25 mph, or 10% of the time
 - Expect that up-conversion is a problem at significantly lower wind speeds & a large fraction of the time
- External Pre-Isolation (EPI) Upgrade is required to allow both reliable locking and to allow better noise performance while locked
 - Prototype testing at LASTI facility has demonstrated 10x reduction in 0.5 to ~2.5 Hz band (compared to 15x reduction requirement in the 1-3 Hz band); testing and optimization continues
 - Design review scheduled for ~4/18
 - Earliest installation start is Oct with completion ~Jan
 - To date have focused on LLO (more acute) problem; Plan to install PEPI systems at LHO for wind noise needs more evaluation.