Status of high power laser development for LIGO at Stanford

Shally Saraf*, Supriyo Sinha, Arun Kumar Sridharan and Robert L. Byer *E. L. Ginzton Laboratory, Stanford University*

LSC2003 Hannover, Germany

August 18-21, 2003

LIGO-G030434-00-Z

*saraf@stanford.edu

Outline

- Stanford approach to power scaling.
- Experimental setup.
- 100W demonstration results.
- Scaling to 200W.
- Future work.

MOPA vs OSCILLATOR



Experimental setup presented at LSC Livingston



End pumped slab geometry*



Results of MOPA experiment

- Single Pass Power output ~ 65 W ($M^2 < 1.1$)
- Depolarization ~ 1.5%.
- P-P intensity fluctuations ~ 7%



COLD SLAB OUTPUT 30 W



PUMPED SLAB OUTPUT 65 W

Mode content of 65 W beam



Double pass setup for MOPA experiment



Slab Issues for scaling to 200W

Question: Why is the small signal gain of the end pumped slab much lower than expected?

Answer: 30 - 35% pump scattered in undoped region.



Solutions towards improved pump confinement

1. POLISH UNDOPED SIDES AND ROUGH UP THE DOPED REGION.



- ++ Small signal gain improved.
- Vendor damaged coating during sand blast procedure for roughening up the doped region.

Measurements on fully polished slab.

2. POLISH THE TWO PREVIOUSLY ROUGH SIDES OF SLAB.



- ++ Pump light guiding improved to 75-80%.
- ----- Parasitic kicks in immediately and clamps the gain.

Measurements on beveled slab

3. POLISH AND BEVEL THE TWO SIDES OF THE SLAB TO KICK OUT THE PARASITIC.



- + Parasitic threshold increased.
- Parasitic still kicking in well before reasonable gain achieved.

Slab with cladding

4. APPLY CLADDING ON DOPED REGION OF SLAB TO SPOIL TIR ANGLE FOR TRANSVERSE PARASITIC.



- **CLADDING USED:** Norland 61 optical epoxy n = 1.56
- PARASITIC LEAKS INTO CLADDING AND IS SCATTERED OUT

Measurements on slabs with cladding



+++ Cladding approach works well for suppressing parasitics.

- Slabs cracked from possible contamination and stresses during polishing.

Parasitic control summary



Scaling to 200 W : Experimental Plan



Saturated amplifier noise experiment tentative setup



Future Work

- Get mode content and noise measurements of 100 W beam.
- Power scale to 200 W using 2 end pumped slabs.
 - Build 2 new slabs with parasitic control cladding.
 - Set up pumping scheme for slab #1 (preamplifier).
 - Measure mode and noise characteristics of 200 W beam.
- Complete saturated amplifier noise experiment.