



Results of the Hardware Injections performed on the LIGO Interferometers


Myungkee Sung for the LIGO Science Collaboration

11th Gravitational Wave Data Analysis Workshop December 18 2006 @ Potsdam, Germany

LIGO Hardware Injections

- Hardware injections are the only direct test of detector time response.
 - ➤ Detector deforms gravitational waveform in a predictable (?) way.
 - > Detector response function quantifies this deformation.
- Injections are also a good test for measuring the absolute size of signal.
- Hardware injections on the S5 run of LIGO
 - Burst/Inspiral injections, pulsar injections, stochastic injections, special injections.
 - > Very little dead time <0.5% of livetime due to burst/inspiral injections
- Analysis consists of successive application of linear filters on raw data (error signal):
 - Whitening filters, applied once and twice.
 - Transformed template (from strain to error signal)
- Diagnostic tool with prompt analysis after each injections.
- KleineWelle analysis of veto safety of auxiliary data channels

Servo Diagram of IFO



• Infer strain *s*(*f*) from observable *DERR*(*f*):

$$s(f) = R(f)DERR(f)$$

• Calibration team measures this detector response function R(t,f):

$$R(t,f) = \frac{1 + \gamma(t)G_0(f)}{\gamma(t)C_0(f)}$$

where open loop gain $G_0(f)$:

$$G_0(f) = D(f)A(f)C_0(f)$$


Detector (true) Strain • $EXC_x(t)$ for hardware injections:

$$EXC_{x}(f) = -h_{inj}(f)/A_{x}(f)$$

Burst Injections


- Twenty different burst waveforms in strain, h(t)
 - > Four Gaussians: $\sigma = 0.3, 1.0, 3.0, 10 \text{ ms.}$
 - ➤ Sine-Gaussians (Q=9) with 12 frequencies from 50Hz to 3068Hz
 - Supernova waveform: Zwerger-Mueller (A3B3G1)
 - \triangleright Cosmic string cusp ($f_{cutoff} = 220Hz$)
 - \triangleright Band-limited white noise burst: f = 250Hz, δ f = 100Hz and σ = 30ms
 - \triangleright Ringdown: f = 2600Hz δt = 30ms
- Various settings of strengths and time for each injections
 - > Same waveform injected to three IFOs with time shifts (if in science mode).
 - Two regular injections daily on average, each with three waveforms.
 - ➤ Loud injections of Gaussians and sine-Gaussian at least once per week for studying coupling to auxiliary channels and impulse response of detector.

Gaussian ($\sigma = 0.3$ ms) injection



• Use actuation function, $A_x(f)$, to calculate the excitation function: $EXC_x(f)$


$$EXC_x(f) = -h_{ini}(f)/A_x(f)$$




• Note: this injection is approximately an *impulse* in strain.

Result of injection


or impulse response






Analyzing Injection Data

- Matlab scripts (python scripts for controlling jobs)
- Use DERR(t) data
- Time windows of 64s, Tukey windowing to use the middle 48s
- Whitening filters
 - Single whitening filter: $sw(t) = \int_0^\infty \frac{derr(f)}{\sqrt{S(f)}} e^{-2\pi i f t} df$
 - Double whitening filter: $dw(t) = \int_0^\infty \frac{derr(f)}{S(f)} e^{-2\pi i f t} df$
 - \triangleright Noise estimate, S(f), from two 50s long data before and after injection period.



Whitened DERR

or whitened impulse response



Optimal Linear Filter

$$||h(t)||=N_{lpha}\int_{0}^{\infty}rac{d_{lpha}^{st}(f)derr(f)}{S(f)}e^{-2\pi ift}df$$


- A standard method from classical signal processing.
- Matched filter study: template from injected waveforms with the detector response function (Calibration):

$$d_{\alpha}(f) = h_{inj}(f)/R(f)$$


- Optimized for the measured stationary noise of detector Double whitening.
- It is also a *linear* measure of the strength;
 - \triangleright Choose normalization so ||h|| is unbiased estimate of true h_{rss} of this waveform.
 - \triangleright Response functions cancel, i.e., the equivalent expressions for either observable DERR(t) or strain s(t).

Filtered output from loud Gaussian

Filtered output from optimal filter at 833364049



- Strength Measurement
 - Injected: 20× 10⁻²¹s^{1/2}
 - Measured: 19.984× 10⁻²¹s^{1/2}
 - rms(noise): 0.0357×10⁻²¹s^{1/2}
- Time measurement
 - Injected time offset: 0.5 s
 - Measured time offset: 0.5001s




Supernova waveform: Zwerger-Mueller (A3B3G1)


- Strength Measurement
 - Injected: 0.6× 10⁻²¹s^{1/2}
 - Measured: 0.661×10⁻²¹s^{1/2}
 - rms(noise): 0.04168×10⁻²¹s^{1/2}
- Time Measurement
 - Injected offset: 0.3555s
 - Measured offset: 0.3558s


Hardware injection monitoring


snapshot of online display for scimons -




Gaussian σ=1ms: Strength Measurement









Gaussian σ=1ms: Time Measurement










Measuring Burst Injections



- Number of injections:
 - H1 5018
 - H2 5958
 - L1 4098









Veto Safety Study using Hardware Injection


- Transients identified by KleineWelle algorithm on auxiliary data channels at the time of injections
- Injections from 272 days of S5 run
- From *DERR*:






Veto Safety Study using Hardware Injection

RMP(Recycling Mirror Pitch) - Safe



• ASI(Antisymmetric port In-Phase) - Unsafe



Summary

- Hardware injection provides very useful tools to understand the performance of interferometers.
- Injections during S5 are analyzed by using
 - Whitening filters
 - Optimal linear filters
 - KleineWelle algorithm
- Prompt result from hardware injections is available and used as a diagnosis tool.
- From statistical study, detector response to injected waveforms is analyzed.
- Veto safety study on auxiliary data channels with transients from KleineWelle algorithm.