


Enhanced LIGO Status

Michael Landry
LIGO Hanford Observatory


PAC24
Jun 23, 2008
LHO






Status

- Enhanced LIGO
 - » Factor of ~ 2 improvement in reach of the two 4km instruments (nearly order-of-magnitude improvement in rate)
 - » All upgrades make use of Advanced LIGO technology: vet and learn
 - » Enhanced LIGO is well underway - the majority of installation is complete. Currently locking both instruments. At least one significant vent and one minor vent remain at each site.
 - » Aggressive schedule; \sim few months behind our original markers



- AEI/LZH 35W laser: first stage of AdL laser. Uses AdL CDS controls
- Pump diode and electronics room complete at both sites
- PSL installed, running at LHO. Install at LLO: mid July

PSL




Pump diode room

PSL




- 35W PSL installation completed smoothly at LHO
- Pump-diodes operating in new (AdL) external laser diode room
- All PSL servos (FSS, ISS, PMC) have operated at eLIGO levels
- IO high power working nominally
- Mode-matching into suspended mode-cleaner complete, with 97% visibility


more PSL




LHO diode room

- Electro-optic modulator
 - » 30-50X less thermal lensing than iLIGO units
 - » 3 frequencies in single unit






- Faraday isolator
 - » Two TGG rotators interleaved with quartz
 - » Polarization and thermal compensation



Septum and HAM4

HAM4 mods at LLO



Installing the window at LLO





Installing the septum at LHO



Active seismic (SEI) isolation

- Two active seismic isolation systems on 4k interferometer outputs
- Six onboard GS-13 seismometers and six position sensors measure velocity and position
- Feedback to six coil actuators
- First unit built and tested at High Precision Devices, Inc
- Next unit assembled, installed and locked down at LLO
- First unit rebuilt (clean) at LHO, installed, currently under commissioning



Testing at HPD, Boulder last November

N.B. ISI = "internal seismic isolation"
(in case I say it).



LIGO-G08



Installation into HAM6



AVI at LLO elog, Fri Mar 7, 2008

LIGO-G080387-00-D

Landry - PAC24, 23 Jun 2008

Installation into HAM6







SEI status


- LLO
 - » Table floating in vacuum, with payload
 - » Passive (pendulum) isolation only
- LHO
 - » All damping loops closed and running
 - » All control loops for six degrees-of-freedom designed and implemented - with unity gain frequencies of about 25Hz, but missing some low frequency performance
 - » Work on low-frequency sensor correction underway



OMC, DC readout



- Output Mode-Cleaner (OMC)
 - » RF detection limited by photodiode saturations
 - » OMC rejects junk light and higher order modes
 - » Critical for AdvLIGO
 - » First OMC assembled and tested, installed at LLO
 - » Resonated TEM00 mode
 - » *Locked full interferometer with DC readout!*
- OMC suspension
 - » Double suspension provides passive isolation > few Hz
 - » First unit built at CIT, suspended OMC board: assembled at LLO
 - » *Fabrication of 2nd unit pacing next vent at LHO*


OMC with SUS










Thermal compensation system (TCS)




- Require several W of CO₂ power to compensate for heating by NdYAG beam at 30 W input power
- Use axicons to make a donut out of Gaussian beam
- Team TCS on site: installation and commissioning




- Additional tasks such as
 - » earthquake stop retrofit. Potential to reduce charging noise, as observed in L1 during S5. All test masses.
 - » Mode cleaner drag wiping, baffle (scatter site) removal, etc



Other: magnet swap




- Low-frequency upconversion observed, understood to be Barkhausen noise
- Swap NdFeB magnets for SmCo on end-test masses
- Complete at LHO; July swap for LLO



Landry - PAC24, 23 Jun 2008

What's left to do?

- Also
 - » LLO: magnet swap (paces LLO)
 - » LLO: loops on HAM6 ISI
 - » Both: baffles, sundry in-chamber, TCS
 - » LHO : ITM alignment
 - » All : integrated commissioning






LHO highlights

- LHO running at high power
 - » 35W on PSL table, currently only up to 7W into mode cleaner
 - » Interferometer relocked with new laser, new input chain, new alignment, using RF (only - no DC readout yet)
 - » Adding TCS this week - will pave the way for high-power tests
- HAM6 ISI nearly commissioned
 - » Have not made noise performance evaluation yet, but expect to meet or exceed AdL spec
- July vent
 - » Baffle installation
 - » ITM realignment/debiasing
- OMC being assembled on site this week
- Expect OMC SUS late July - land OMC on HAM table early August



Beginning to measure noise at LHO






LLO highlights

- LLO locking with DC readout
 - » OMC is fully operational in vacuum (transmission ~90%, mode matching ~90%)
 - » Measured noise couplings to DARM in full lock: laser intensity and oscillator phase. So far no surprises or show stoppers
 - » PRC correction signal is down by a few hundreds indicating that coupling is also lower
 - DC DARM noise is mostly shot noise limited above 1 kHz .
 - OMC length and angular control loop noise investigations underway (contributing above 200Hz?)
- July vent
 - » Baffles
 - » ETM magnet swap




4Mpc at LLO





Summary

Primary
Enhanced
LIGO installs
complete...






Summary

Primary
Enhanced
LIGO installs
complete...

commissioning
is underway,






Summary


Primary
Enhanced
LIGO installs
complete...

commissioning
is underway,

a natural step
towards
Advanced
LIGO



Detection, and transition to full-fledged GW astronomy are not far off





Noise and the enhanced detector

