

**NSF Presentation -
Seismic Isolation System
Procurement Plan**

S. Whitcomb

10 June 1997

**Procurement Sensitive Document-
Do Not Distribute**



Outline

- **System Description and Status**
- **First Article Program and Production Schedule**
- **Procurement Plan**
- **HYTEC Contract Modification**
- **Summary**

Seismic Isolation: Subsystem Overview

- **Provides vibration-isolated mounting surfaces for all in-vacuum optical components**
- **Two types of seismic isolation stacks**
 - ››BSC Chambers (10 in WA, 5 in LA)
 - ››HAM Chambers (8 in WA, 4 in LA)
- **On critical path for detector installation**
 - ››Must be in place before anything else can be installed in vacuum
- **Most expensive detector subsystem**
 - ››Approximately \$12 M (~20% of detector budget)

Seismic Isolation: System Status

- **Preliminary Design Review held 3/5/97**
 - ››HYTEC authorized to initiate final design of seismic isolation system
- **Tests of constrained-layer-damped metal springs continue to be promising**
 - ››All fabrication techniques developed
 - ››Load capacity, stiffness, damping
 - ››Acoustic transmission tests show adequate attenuation
 - Tests for creep, creak to begin next week
- **Final design/fabrication plan reworked (using vendor estimates of fabrication times) to include first article fabrication and testing**

First Article: Goals

- **Reduce design risk before starting full fabrication**
 - ›› Test actuators for smooth operation
 - ›› Check for fit - eliminate interferences
 - ›› Test assembly tooling and fixtures
- **Gain assembly experience early**
 - ›› Train staff that will be installing seismic isolation system before starting real installation
- **Fabricate 1 stack of each type for testing plus some long-lead items for additional stacks with early need dates**
 - ›› 1 BSC stack for testing
 - ›› 1 HAM stack for testing
 - ›› Long-lead (and low-risk) components for 2 additional HAM stacks

Seismic Isolation: Schedule

- **Complete First Article fabrication drawings and review - June/July 97**
- **Issue RFQ's for First Article - June/July 97**
- **Issue contracts for fabrication - Aug 97**
- **Begin First Article assembly - Nov 97**
- **First Article test complete - Jan 98**
- **Rework HAM First Articles (if needed) - Feb/Mar 98**
- **Final design review - Mar 98**
- **Issue final production awards - Apr/May 98**
- **Start First Article installation - Apr 98**
- **Start production stack installation - Oct 98**

Overall Procurement Summary

Element	First Article Cost		Production Cost	Procured By	Procurement Type
Bellows	1 BSC 1 HAM	\$70 k	\$500 k	Caltech	Build-to-Print w/ priced Option
Metal Springs	420 springs	\$150 k	\$850 k	Caltech	Build-to-Print w/ priced Option
Optical Tables	1 BSC 3 HAM	\$40 k \$50 k	\$305 k	Caltech	Build-to-Print w/ priced Option
Actuators	1 BSC 1 HAM	\$185 k \$110 k	\$2,600 k	HYTEC (First Art) /Caltech (Prod.)	Multiple POs (Catalog Items)
Stack Hardware	1 BSC 3 HAM	\$85 k \$185 k	1,340 k	HYTEC (First Art) /Caltech (Prod.)	Build-to-Print Contract
Non-vacuum Hardware	1 BSC 3 HAM	\$20 k \$60 k	\$390 k	HYTEC (First Art) /Caltech (Prod.)	Build-to-Print Contract
Vacuum Support Hardware	1 BSC 3 HAM	\$35 k \$55 k	\$510 k	HYTEC (First Art) /Caltech (Prod.)	Build-to-Print Contract
Assembly Fixturing	1 BSC 1 HAM	\$100 k \$100 k	\$200 k	HYTEC (First Art) /Caltech (Prod.)	Build-to-Print Contract



Procurement Plan: Bellows

- **LIGO requirement for range exceeds normal industry practice**
- **Several vendors contacted by HYTEC to solicit prototype**
- **Only one vendor (Senior Flexonics) would fabricate to LIGO requirements**
- **Prototype unit on order (by HYTEC)**
- **Plan: Caltech to issue RFQ for First Article (8 bellows) with priced Option for 124 additional units**
 - ›› Will send RFQ to multiple vendors
 - ›› Possible that only Senior Flexonics will respond
- **Award First Article contract Aug 97**
- **Exercise production Option Jan 98**

Procurement Plan: Metal Springs

- **Significant development effort to date to define manufacturing processes and to train vendor in manufacturing technique**
- **Only one vendor (Pegasus) qualified**
- **6 prototypes fabricated to date (HYTEC contract)**
- **Plan: Caltech to issue RFQ for pre-production run (420 springs) with priced Option for 3400 additional units**
 - ››Sole source based on time required to develop alternates
- **Award First Article contract Aug 97**
- **Depending on Option price (HYTEC has developed independent target price), begin development of second source**
- **Exercise Option Jan 98, or rebid**

Procurement Plan: Optical Tables

- **HYTEC/Caltech in process of qualifying multiple vendors (weld specimens, cleaning techniques, etc.)**
- **Important to stay with qualified vendor after First Article test; not enough time to requalify/rebid**
- **Plan: Caltech to issue RFQ for First Article (1 BSC, 3 HAMs) with priced Option for remaining units**
 - ›› Will send RFQ to multiple vendors
 - ›› Expect multiple bids
- **Award First Article contract - Aug 97**
- **Exercise production Option - Mar 98**

Procurement Plan: Actuators

- **Almost all actuator components are commercial catalog items**
- **Multiple vendors**
- **Will purchase on standard P.O.'s**
- **HYTEC to specify as part of design and to procure First Articles for test**
- **Caltech to purchase all remaining production units**

Procurement Plan: Hardware and Fixturing

- **Includes stack hardware, non-vacuum hardware, vacuum support hardware and assembly fixturing**
- **All to be fabricated via competitive build-to-print contracts**
- **No special need to continue with the First Article vendor for production units**
- **Plan: HYTEC to issue First Article fabrication contracts (at least 4) - Aug 97**
- **Caltech to bid and award production contracts - Apr/May 98**

HYTEC

- **Original LIGO contract to investigate damped metal springs**
- **Based on success, expanded to provide engineering support services for seismic isolation design, fabrication, test**
- **Experienced with similar problems**
 - ›› Bill Miller, President
 - Sr. Mechanical Engineer-Los Alamos National Lab (>20 years)
 - Experience with highly stable, low vibration opto-mechanical structures for Laser Fusion
 - ›› Tim Thompson
 - Mechanical Engineering Group Leader at LANL
 - Expert in precision mechanical structures and mechanisms
 - ›› Eric Ponslet
 - Ph. D. Mechanical Engineering
 - Led damped metal spring development effort

HYTEC Contract: Proposed Modification

- **Builds on experience of HYTEC with LIGO seismic isolation system and similar projects at LANL**
- **Adds labor for First Article fabrication and testing**
- **Adds labor for assembly fixture design, build and test**
- **Adds labor for manufacturing oversight and installation support**
- **Adds funds for First Article procurements to be done by HYTEC**
- **Current Contract \$1865 k**
- **Proposed modification \$1642 k**
 - ›› Labor \$708 k
 - ›› Material \$934 k



Summary

- **Seismic Isolation system design maturity permits First Article fabrication and test**
 - ›› Reduces design and performance risk
 - ›› Reduces cost uncertainty
 - ›› Gain assembly experience early to reduce schedule risk during integration
- **Procurement plan developed to:**
 - ›› Move quickly on critical path subsystem
 - ›› Preserve competitive bidding
 - ›› Allow development of second sources if needed
- **What do we want?**
 - ›› Approval of HYTEC contract modification
 - ›› Comments and suggestions about overall procurement plan - any NSF concerns?
 - ›› Advice on NSF approval process for First Article and production subcontracts