

aLIGO SUS Acceptance Test Criteria
E1200844-v1

For a given type of suspension

- Design Document
 - Requirements document
 - Conceptual design documents
 - Final design documents
 - Control system design documents
- Full Mechanical Assembly Package
 - Drawings
 - As-built Solidworks assembly
 - As-built mechanical assembly procedure
 - Installation procedure
- Full electronics drawing package
 - As-built circuit schematics
 - Full signal chain electronics layout (wiring diagram)
 - Full signal chain description (block diagram)
 - Compensation vs. state description
 - Design description
 - Model of circuit which can predict
 - Transfer functions
 - Noise performance in terms of
 - Input and Output referred voltage noise
 - Current noise across coil
 - Force noise on optic
 - Displacement of optic
- Dynamical model, with fully cross-coupled DOFs (as necessary), and representative damping loops
 - Matlab / Mathematica models stored in SVN / DCC
- Dynamical model results package which contains
 - Commonly-asked-for Transfer functions (Matlab, Mathematica)
 - Mode shapes (Mathematica)
 - Predicted residual seismic motion (Matlab, Mathematica)
 - Predicted residual sensor noise (Matlab)
 - Predicted residual actuator noise (Matlab)
 - Predicted maximum range of motion (Matlab / Spreadsheet)
- Testing software package (as automated as possible)
 - Transfer functions
 - ASDs
 - Range
- User's manual

For a single suspension

All analog & digital systems complete as designed

- Full (control) signal chain for all stages in place and confirmed functional as designed
 - Sensor calibration understood/independently confirmed (at least for representative sensors on chain, independently calibrated by... VCO?)
 - Calibrated sensor channels stored in frames
 - range/signs understood (DC range test, compare against range document, signs check out with Sign Table)
 - ASD spectra understood (Spectra compared against sensor noise and

seismic into SUS point)

- BIO completely functional (TEST/COIL out switch confirmed via ability to drive, frequency response switches confirmed with monitor chassis transfer functions)
- All possible states of Frequency response of sensor chain and drive chain are confirmed
- Electronics compensation filters have confirmed compensation to ~5% from DC to several kHz
- Drive noise performance understood (matches expected noise level), matching expectations compared against requirements in Current, Force, and Displacement (ASDs of NoiseMon's turned "propagated" through models)
- Undesired cross-coupling characterized / compensated / minimized
 - Technical
 - Sensors
 - Actuators
 - Fundamental / Mechanical
 - Longitudinal to Pitch
 - Others (?)
- Control hierarchy defined as designed
- Monitor Chassis
 - Monitor signals with MEDM (yes/no)
 - Noise performance confirmed functional (ASD of all OSEMs on all stage's NoiseMon channels)
 - Calibration understood
 - Calibrated channels in frames (yes/no)

Mechanical TFs (open loop "plant" for locking / damping loops) check out

- As-installed (Phase 3b) TFs, compared against model and other SUS of same type / assembly level
- Comparison of "Passed" TF all phases of testing show same results

Structural resonances are at acceptably high frequency

- As-installed, driven (B&K Hammer & ISI) transfer function confirmation

Damping loops perform as best as possible, as expected from full production model

- Closed loop gain
- Open Loop Gain
- ASDs and RMS motion match predictions given input in
 - L (with cavities if possible)
 - P and Y (with optical levers, if possible)
 - (others if possible)

As-installed Mechanics / Sensors / Actuators / Electronics inventoried

- Fundamental properties measured
 - Mechanics
 - Optic S/N, associated mechanical properties (mass, radius, thickness)
 - Level of assembly vs. retrofits (flat flags, pitch adjusters, ECD magnets, etc)
 - Overall mass of each stage, as-installed
 - Trim mass distribution
 - Lowest stage characterization (violin mode frequencies; for fibers & ears: metrology)
 - Actuator / Driver
 - Serial numbers

- Coil Resistance / Inductance (of full chain, preferably, but at least once along the phases of testing)
- Driver noise level (as measured on the bench during phase 1a, and from noisemon circuits in situ)
- Frequency Response of Full Chain in all states
- Magnet characteristics
- Sensor
 - Serial numbers
 - Open light voltage / Calibration
 - Sensor noise level
 - Frequency Response of Full Chain
- Other associated Electronics (AA, AI, I/O Chassis, BIO Chassis, etc.)
 - Serial numbers
 - Associated during-assembly test results